PROPOSED SR 254 CURVE DATA

PI STA 104+99.00
Δ = 6°-15'
D = 1°-00'
T = 312.81'
R = 5729.58'
L = 625.00'
E = 8.53'

EXIST. 10" MEDIUM PRESSURE GAS LINE

STA 105+02.90 SR 254
STA 25+09.52 ABBE RD.

℄ SR 254

STA 104+99.00 SR 254 TAN
STA 25+00.00 ABBE RD.

N 62°-45'-24"E
168.20'

SR 254 PAVEMENT

PROPOSED BLACKTOP

TRAFFIC DIVIDERS

100.00'

EXIST. 8" WATER MAIN

PROPOSED 12" WATER LINE

2' BOTTOM DITCH

27" CONC. PIPE STORM SEWER

EXIST. 8" WATER LINE

PROPOSED 8" WATER LINE

6" GAS LINE

WATER VALVE

HYD.

STD. NO. 2-2A CATCH BASIN

15" CONC. PIPE

STORM SEWER

STD. NO. 5 CATCH BASIN

EARTH DIKE

ABBE RD. PAVEMENT

℄ ABBE RD.

20:1 TAPER

N 02°-19'-24"E
158.57'

N 62°-49'-41"E
126.68'

R/W LINE

WOOD HUB R/W LINE

STA 106+60.44
66.189'

IRON PIN 24"

STA 107+50
65'

IRON PIN

PROPERTY LINE

3-00-002-A

03-00-002-102-023
026

AREA = 0.506 ACS.

LAWN

RASPBERRY BUSHES

SPRINKLERS

N 06°-04'-55"E
109.02'

S 19°-14'-36"E
145.04'

S 19°-14'-36"E
167.59'

S 81°-50'-24"W
124.91'

S 76°-32'-22"W
99.53'

49.77'

174°-41'-58"

84°-13'-02"

① STA 24+00, 44' LT.
STD. NO. 2-2 A C.B.
675.3 TOP OF C.B
669.30 ft C.B & 15' PIPE OUT OF C.B.

② STA 24+00, 41.5' RT.
STD. NO. 5 C.B.
668.45 ft 15" PIPE INTO C.B
667.45 ft C.B. & 27" PIPE INTO & OUT OF CB

LEGEND

WATER LINE	SHEFFIELD VILLAGE
GAS LINE	COLUMBIA GAS OF OHIO
TELEPHONE POLE	LORAIN TELEPHONE COMPANY
POWER POLE	OHIO EDISON COMPANY
WATER VALVE	

SCALE 1" = 10'

B.M. BOAT SPIKE IN ROOT OF 15" W. CHERRY 18' LT. STA 17+86 ABBE ROAD ELEVATION 678.92

B.M. BOAT SPIKE IN POWER POLE 27' RT. STA 105+14 STATE ROUTE 254 ELEVATION 679.75

SURVEY FOR STANDARD OIL COMPANY CORNER OF STATE ROUTE 254 AND ABBE ROAD

SHEFFIELD TOWNSHIP, LORAIN COUNTY, OHIO

T-7N R-17W

SEPTEMBER 21, 1966
BY SHELBY J. EDWARDS
REG. SURVEYOR NO. 3925